

2000 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 09E	C-4 ✓
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Alcona County
Remonumentation
Liber 2 Page 90

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:54 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 3-30-2000, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
1843 - James A. Mullet: Set post and witnessed
1996 - Northeast Land Surveys (Bill Woods, P.S.): Found 1/2" rebar, no witnesses given


APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date. 9-6-2000
County Rep. W.T.L.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" rod @ surface, 3' East of road c/l, cut line to the East and remnants of old fence to the West
This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
2000 - Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rod driven next to pipe found under existing rod in mon. box

Witnesses:
S 40° E 37.60' .6" W. Pine (set tag #41922)
S 35° W 39.52' 15" W. Birch (set tag #41922)
West 33.01' Rerod w/cap #25882
N 85° W 76.65' 26" Twin Maple (set tag #41922)
N 50° W 32.84' 12" Poplar (set tag #41922)



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date September 14, 2000

SURVEY &
REMONUMENTATION

FEB 07 2001

SECTION