

2000 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in <u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 09E	C-5 ✓
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Alcona County
Remonumentation
Liber 2 Page 91

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:54 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 3-30-2000, 19__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1843 - James A. Mullet: Set post and witnessed
1902 - E. Chapelle, C.S.: Set large gray boulder w/crockery under it and witnessed
1972 - Richard L. Miller, P.S.: Found 1" iron pipe in intersection, and recorded LCRC in 1983 (L 1, P 119), and witnessed
1977 - John F. Oliver, P.S.: Found 1" pipe and recorded LCRC (L 1, P 49) and witnessed
1996 - Bill Woods, P.S.: Found 1/2" bar, no witnesses given


APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 9-6-2000
County Rep. Det. B. C. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 1/2" smooth iron rod, 1.5' East of Coville Rd. and 2' North of Wissmiller Rd.

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
2000 - Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rerod driven next to 5/8" rod in mon. box

Witnesses:
N 25° E 70.25' 8" Red Pine (set tag #41922)
S 60° E 33.09' 28" Maple (exist. spike in deep scar, set tag #41922 on opposite side of tree)
S 35° W 63.80' Power Pole (set tag #41922)
N 70° W 60.77' Wood Fence Post (set tag #41922)



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date September 14, 2000

SURVEY &
REMONUMENTATION

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1985

FEB 07 2001

SECTION