

2000 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alcona

(County)	Located In:	Corner Code #
1. Public Land Survey	T 25N R 09E	C-6 ✓
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Alcona County
Remonumentation
Liber 2 Page 92

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:54 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 3-30-2000, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1843 - James A. Mullet: Set post and witnessed
- 1902 - E. Chapelle, C.S.: Found post and witnessed
- 1972 - Richard L. Miller, P.S.: Found boat spike in road c/l, and recorded LCRC in 1983 (L 1, P 119), and witnessed
- 1977 - John F. Oliver, P.S.: Found large boat spike, and recorded LCRC (L 1, P 49), and witnessed - Also see field notes

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date 9-6-2000
County Rep. W.T. Lewis

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found boat spike on road c/l and in line w/fence to the West and fence to the East

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2000 - Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rod in place of existing boat spike in mon. box

Witnesses:

- N 35° E 68.66' 10" Maple (set tag #41922)
- N 50° E 59.77' 16" Maple (set tag #41922)
- N 85° E 34.78' 15" Maple (set tag #41922)
- S 40° E 59.36' 12" Maple (set tag #41922)
- East 50.53' 36" Hemlock (exist spike)



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date September 14, 2000

SURVEY &
REMONUMENTATION

FEB 07 2001

SECTION