

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

1994 Alcona County Remonumentation Corner

Alcona County Remonumentation Liber 1 Page 102

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Alcona
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 25N R 9E
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date: 12-21-94
 County Rep. E. J. L.

DEC 21 2 09 PM '94

David A. Benthien
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

E. J. L.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on December 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1839: G.L.O. Survey by Lewis Clason - Set Post and Referenced -
 B.Oak 6 - N53E - 17 / W.Birch - S44W - 18

1949: Survey by R.J. Cooke - Plat of Rettke's Alice Park

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994: Found Railroad spike in Center of Hwy. F-30.
 Fenceline South

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994: Set 5/8" Iron Rod with a 3" Brass Cap stamped to identify the Corner placed in a Monument Box.
 Referenced -
 N10°W - Anchor Pole - 30.24 Feet
 N50°W - 48" Oak - 40.25 Feet
 S50°W - 12" W.Pine - 56.17 Feet
 S05°W - 12" W.Pine - 49.19 Feet



Signed by *David B. Guthrie* Date December 21, 1994

Surveyor's Michigan License No. 22435