

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

1994 Alcona County Remonumentation Corner

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 106

For corners in

<u>Alcona</u> <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T <u>25N</u> R <u>9E</u>	<u>I-6</u>	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY  
Date 12-28-94  
County Rep. E.J.L.

Dec 28 10 05 AM '94

*Janis A. Smith*  
REGISTER OF DEEDS  
ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

David B. Guthrie in a field survey on December 23, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

1843: G.L.O. Survey by Mullett & Burt - used 14" Cedar for Corner.  
No references.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Set 5/8" Iron Rod by the extension of the West Line of the Southwest 1/4 of Section 14 as evidenced by the Plat of Huron-Cedar Lakes Subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Replaced with a 5/8" Iron Rod with a 3" Aluminum Cap stamped to identify the Corner.  
Referenced -  
S47°E - 8" Ash - 42.49 Feet  
S32°W - 6" Birch - 117.79 Feet  
N89°W - Twin 10" Maple - 107.10 Feet  
N60°E - Twin 14" Maple - 102.72 Feet



Signed by David B. Guthrie Date Dec. 28, 1994

Surveyor's Michigan License No. 22435