

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

Alcona  
(County)

Located In: \_\_\_\_\_ Corner Code: \_\_\_\_\_

1. Public Land Survey T 25N R 9E I-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 ALCONA COUNTY

Date 12-21-94  
 County Rep. E.T.L.

DEC 21 2 10 PM '94

*Janie A. Smith*  
 REGISTER OF DEEDS  
 ALCONA COUNTY MICHIGAN

*E. T. L.*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

David B. Guthrie in a field survey on October 24, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: G.L.O. Survey by Mullett & Burt - Set Post and Referenced W.Pine 14 - N69W - 15 / W.Pine 18 - S14W - 30
- 1941: Survey by Ora F. Gould - Plat of Huron-Cedar Lakes No. 1
- 1965: Survey by John C. Miller - Supervisor's Plat of Greenbush Beach
- 1966: Survey by Russell M. Small - Found Concrete Monument, no references. Plat of Irwindale

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found Concrete Monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Capped Concrete Monument with a 3" Aluminum Cap stamped to identify the Corner.

- Referenced -
- West - 24" W.Pine - 32.43 Feet
  - S39°W - 20" W.Pine - 41.02 Feet
  - N26°E - 12" W.Pine - 4.76 Feet
  - N20°W - 15" R.Pine - 29.38 Feet



Signed by David B. Guthrie

Date Dec. 21, 1994

Surveyor's Michigan License No. 22435