

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

1994 Alcona County Remonumentation Corner

Alcona County Remonumentation
Liber 1 Page 93

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

<u>Alcona</u> (County)	Located in:	Corner Code
1. Public Land Survey	T <u>25N</u> R <u>9E</u>	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY

Date 12-21-94
County Rep E. J. L.

DEC 21 2 10 PM '94

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, David B. Guthrie in a field survey on October 14, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1843: G.L.O. Survey by Mullett & Burt - used 18" Hem for Corner
No references.
 - 1939: Survey by R.J. Cooke - Plat of Greenbush Acres Sub. No. 2
 - 1955: Survey by Clarence F. Aikman - Plat of Huron-Cedar Lakes Sub. No. 5
 - 1971: Survey by Edward LaCross
 - 1972: Survey by Richard L. Miller
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - 1994: Found Concrete Monument

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 - 1994: Capped Concrete Monument with a 3" Aluminum Cap stamped to identify the Corner.
Referenced -
 - North - Concrete Monument - 66.00 Feet
 - East - 24" Maple - 2.54 Feet
 - S05°E - 6" Cedar - 11.87 Feet
 - S75°W - 8" Cedar - 5.51 Feet
 - N45°W - 8" Cedar - 6.72 Feet



Signed by *D.A. Guthrie* Date Dec. 21, 1994
Surveyor's Michigan License No. 22435