

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25 NR. 9E

Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 28, 29, 32, 33

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

8" B. Oak - N44W - 92 1/2 links

7" R. Oak - S60W - 47 links

5" W. Oak - S70E - 57 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 2 miles north, 1 mile south, 1 mile east, 2 miles west by Forestry Division survey crew. Could make no positive identification of government corner, although our point checks good with swamp edges east, west, north and possibly south which is quite indefinite.

Corner placed and witnessed May 8, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ottling* DATE 6/5/58
REGISTERED LAND SURVEYOR