

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 9E. . .

Alcona COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 19 & 20

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER

6" Cedar - S11E - 92 1/2 links

6" Cedar - S68E - 97 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew. Could make no identification of government BT's., a Fir and a Cedar. A cutting edge extends about 1 chain east of our corner to a blazed line which appears to have been run due south, magnetic bearing, from the section corner north, but can find nothing to support that longitudinal position.

Corner placed and witnessed May 9, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 6/6/58
REGISTERED LAND SURVEYOR