

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 9E. . . .

----- Alcona ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 20 & 29 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap -----

WITNESSES TO CORNER -----

6" Cedar - West - 17 1/2 links -----

8" Cedar - N3W - 25 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between section corners by Forestry Division survey crew. Could not identify Cedar corner tree although many stumps are available. A Cedar blazed 3 sides stands about 1 chain north of the same longitude, which I take to be a cruise line east and west.

Corner placed and witnessed May 9, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Ostling DATE 6/6/58
REGISTERED LAND SURVEYOR