

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 9E. . .

----- Alcona ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 19, 20, 29, 30

DESCRIPTION OF CORNER MONUMENT 1" pipe, with 4" brass cap

WITNESSES TO CORNER -----

4" Cedar - N25E - 46 $\frac{1}{2}$  links

5" Cedar - N76W - 42 links

6" Cedar - S20W - 76 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile north, 2 miles south, 2 miles east and 1 mile west by Forestry Division survey crew. Could find no conclusive evidence of the government BT's. Found an old Tamarack stub which appeared to have been cut into as though having been inspected for marks, but could find nothing set relative to this point, which would have placed the corner about 60 links east of our corner and far from conformity with the first stream crossing east which our corner checks very closely.

Corner placed and witnessed May 9, 1958.

SURVEYORS SEAL

SIGNED Kenneth J. Otting  
REGISTERED LAND SURVEYOR

DATE 6/6/58