

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 25. NR. 9E.

Alcona COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 20, 21, 28, 29

DESCRIPTION OF CORNER MONUMENT

WITNESSES TO CORNER

12" R. Oak - S50W - 38 links

8" R. Oak - N44W - 90 1/2 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by double proportionate measurement between corners 1 mile north, 1 mile east, 2 miles south and 2 miles west by Forestry Division survey crew. Could make no identification of original BT's. This point conforms more closely to the swamp edge north than a square concrete monument which is 1.02 chain south and 25 links east of our corner, by unknown surveyor and not of record. Did not seem justified in accepting this corner which makes the mile north 81.00 at the expense of the two miles south, when nothing definite could be found for government evidence.

Corner placed and witnessed May 9, 1958.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling*
REGISTERED LAND SURVEYOR

DATE 6/6/58