

MAR 03 2000

1999 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in  
Alcona  
(County)

Located In: Corner Code #

1. Public Land Survey T 26NR 06E D-5  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

Alcona County  
Remonumentation  
Book 2 Page 39

19 0  
Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 12-17-1999 At 11:01 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wayne T. Lewis, in a field survey on 9-24, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1846: James Mullet set post and witnessed
- Unknown Date: MDOT Plans: 1" iron bar and witnessed
- 1986: D.R. MacNeill, P.S. found mon. box, no witnesses given
- 1998: J. C. Kapelczak, P.S., fd 1/2" bar in conc. mon. box and recorded LCRC (L3, P77) and survey (L324, P846) and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron rod in mon. box, 6' North of E/W C/L  
This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date 11/30/99  
County Rep. W.T. Lewis

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rerod driven next to iron rod

- Witnesses:
- S 45° E 112.65' 8" Maple
  - S 30° E 76.50' 6" White Pine
  - South 82.58' ROW monument
  - South 73.96' ROW monument



Signed by Wayne T. Lewis  
Surveyor's Michigan License No. 41922

Date December 16, 1999