

MAR 03 2000

1999 Alcona County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alcona

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 26NR 06E E-5
 T ___ R ___
 T ___ R ___
 T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

Alcona County
Remonumentation
Plat 2 Page 40

19
0
Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 11:01 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 9-24, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1846: James Mullet set post and witnessed
- 1912: W.S. Freer found original corner, no witnesses given
- Unknown Date: MDOT Plans: 1" iron bar and witnessed
- 1976: Robert A. Griffin, P.S., found axle shaft and witnessed
- 1987: Sammy S. Barnett, P.S., found 1" axle shaft
- 1997: W. E. Woods, P.S., found corner, no monumentation or witnesses given
- 1998: J. C. Kapelczak, P.S., found capped iron and recorded survey (L324, P845) and LCRC (L3, P74) and witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron rod 22' North of C/L E/W, and in line with C/L N

This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date: 11/30/99
County Rep. Paul R. C.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Placed 3" Alcona County cap, stamped to identify the corner, on 1/2" rerod driven next to iron rod

Witnesses:

- S 10° E 61.32' NE corner concrete headwall East side of drive
- S 10° W 66.08' NW corner of conc. headwall West side of drive
- S 09° W 136.22' Power pole
- S 45° W 59.50' Most E'ly corner post of guard rail top and center
- N 70° W 198.35' Power pole
- N 10° W 175.58' Power pole



Signed by Wayne T. Lewis
Surveyor's Michigan License No. 41922

Date December 16, 1999