

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in Alcona

Located in: Corner Code #

- 1. Public Land Survey T 26N R 06E G-8
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Alcona County Remonumentation Book 2 Page 48
Filed for Record in ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 12-17-1999 At 11:01 am.
LAND CORNER 9.00
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Wayne T. Lewis, in a field survey on 9-24, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 and a black dot at row 8, column H.

A. Description of original monument and accessories and/or subsequent restoration:

- 1846: James Mullet set post and witnessed
1982: D.R. MacNeill, P.S. set 1" pipe and recorded surveys (L187, P716; L209, P455; and L194, P960) and witnessed
1984: R. A. Griffin, P.S., fd 1-1/8" pipe w/cap & set 6" round conc. mon. w/brass cap & recorded LCRC (L1, P152) & witnessed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd. conc. mon. w/brass cap stamped to identify corner w/#13584, corner is 4' East of road C/L & in line w/survey line to the West
This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.


APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 11/30/99
County Rep. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1999: Used existing concrete monument w/brass cap as remonumentation corner

Witnesses:

- S 05° E 44.49' 13" Oak (found dip)
S 80° E 27.33' 10" Oak w/spike (tree is dead)
S 85° E 19.39' 14" Oak
N 20° E 18.83' 8" Oak w/bearing tree tag and spike
N 70° W 27.69' 10" Oak w/bearing tree tag



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date December 16, 1999