

**SURVEY & REMONUMENTATION**

**FEB 07 2001**

2000 ALCONA COUNTY REMONUMENTATION CORNER

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T26NR7E	A-1, Millen Twp.
	T27NR7E	A-13, Hawes Twp.
	T26NR6E	M-1, Millen Twp. ✓
2. Property Controlling in Section	T27NR6E	M-13, Mitchell Twp.
	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Alcona County  
Remonumentation  
Liber 2 Page 78

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 09-20-2000 At 09:42 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

T26N-R7E

	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Thomas L. Fabis, in a field survey on Sept. 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1838: G.L.O. Survey Lewis Clason set post & referenced: Y. Pine 9 S29W 45, Cedar 8 N58E 10  
1989: NELS Survey Liber 323 Page 984 John Oliver found 1/2" bar.  
1998: NELS Survey Liber 326 Pages 859 & 860 Bill Woods measures to the corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
2000: Found 1/2" iron rod in the centerline of E-W (Bit. surface) Trask Lake Road, 2' East of centerline of gravel road to the North and 5' West of centerline of gravel road to the South. No existing witnesses.

The position of this corner is compatible with local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
2000: Set 3" dia. brass cap, stamped to identify the corner, over the existing 1/2" iron rod. Set Mon. Box over corner. Set tag #31591 in the following witnesses:  
Fe. Cor. Post N30E 59.27  
7" Cedar S57E 62.45  
6" Twin Oak S30W 57.96  
8" W. Pine N31W 71.85

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date: 8-28-2000  
County Rep. [Signature]

Signed by Thomas L. Fabis Date September 12, 2000  
Surveyor's Michigan License No. 31591

