

SURVEY & REMONUMENTATION

FEB 07 2001

SECTION

2000 ALCONA COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T26N R7E	C-3 ✓ Millen Twp.
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Alcona County
Remonumentation
Liber 2 Page 77

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 09-20-2000 At 09:42 am.
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Thomas L. Fabis, in a field survey on Sept. 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5			4		3		2		1	
3		●										
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey Lewis Clason set post & referenced: W. Pine 12 S45W 15, do 18 N70E 29
- 1907: County Survey Edward Chapelle found post & orig. B.T.'s.
- 1909: County Survey W.S. Freer Pine stake 4x4 and orig. B.T.'s.
- 1965: Co. Hwy. Plans set 3/4" pipe & referenced.
- 1977: L.C.R.C. Liber 1 Page 48 John Oliver 3/4" iron pipe & referenced.
- 1989: U.S.D.S. Forest Service Survey L.232 P.907 & 908 and L.C.R.C. L.1 P. 407 by John Korr Found 1" iron pipe & replaced with 5"x5"x36" conc. mon. w/brass cap & referenced.
- 1994: Revised R.S.Scott Survey Liber 271 Pages 102-104 David Guthrie No description of corner given, but referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 2000: Found concrete monument w/Forest Service brass cap 15" below grade in the centerline of N-S (paved surface) Stout Road and in the centerline of gravel road to the East (Walker Rd.). Found the following blazed witness trees: S36E 83.80 22" R. Pine, N74W 41.81 12" R. Pine, N50W 59.11 12" R. Pine, N65E 103.77 8" J. Pine
Also found carsonite post 33' West.

The position of this corner is compatible with Federal and local surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 2000: Extended existing Forest Service Conc. Mon. with 1/2" iron rod encased in concrete capped with 3" dia. brass cap, stamped to identify the corner. A Mon. Box was installed over the corner. Witnesses are:

- 22" Blazed R. Pine S36E 83.80
- 12" Blazed R. Pine N74W 41.81
- 12" Blazed R. Pine N50W 59.11
- 8" Blazed J. Pine N65E 103.77
- Carsonite post West 33'

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date 8-28-2000
County Rep. Det. B. Gunt

Signed by Thomas L. Fabis Date September 12, 2000
Surveyor's Michigan License No. 31591

