

**SURVEY & REMONUMENTATION**

**FEB 07 2001**

2000 ALCONA COUNTY REMONUMENTATION CORNER

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T26N R7E</u>	<u>C-4</u> ✓
	T <u>    </u> R <u>    </u>	<u>Millen Twp.</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Alcona County  
Remonumentation  
Liber 2 Page 76

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 09-20-2000 At 09:42 am.  
LAND CORNER 9.00

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Thomas L. Fabis, in a field survey on Sept. 8, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
1838: G.L.O. Survey Lewis Clason set post & referenced: W. Pine 15 N88E 25, do 18 N54W 11  
1965: Co. Hwy. Plans 3/4" pipe & referenced.  
1989: U.S.D.A. Forest Service Survey Liber 232 Pages 907, 908 & 911 and L.C.R.C. Liber 1 Page 407 by John Korr Found 1" iron pipe and replaced with 5"x5"x36" conc. mon. w/brass cap and referenced.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
2000: Found conc. mon. w/Forest Service brass cap 14" below grade in the centerline of N-S (paved surface) Stout Road and the following existing blazed trees:  
N70E 86.97 8" R. Pine, S60E 98.31 8" R. Pine, S89W 68.59 6" Oak, N56W 120.7 12" R. Pine  
Also found carsonite post 33' West.

The position of this corner is compatible with Federal and county surveys and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
2000: Extended existing Forest Service Conc. Mon. with 1/2" iron rod encased in concrete capped with 3" dia. brass cap, stamped to identify the corner.  
A Mon. Box was installed over the corner. Witnesses are:  
Blazed 8" R. Pine N70E 86.97  
Blazed 8" R. Pine S60E 98.31  
Blazed 6" Oak S89W 68.59  
Blazed 12" R. Pine N56W 120.70  
Carsonite post West 33'

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date: 8-28-2000  
County Rep. [Signature]

Signed by Thomas L. Fabis Date September 12, 2000  
Surveyor's Michigan License No. 31591

