

**SURVEY &
REMONUMENTATION**

RECORDED

1994 Alcona County Remonumentation Corner

APR 25 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Nov 7 2 09 PM '94

COMMISSION

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>7E</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

David A. Smith
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Alcona County
Remonumentation
Liber 1 Page 70
E.T.C.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie in a field survey on June 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1846: Survey by J.W. Mullett - Set post and referenced Tam 8 - S58½E - 25 / Tam 6 - S25W - 19
 1920: Survey by Andrew J. Freer - 2"x30" Gas Pipe 15 links east of post
 1939: Survey by George Henning - Set post 15 links west of another post and pipe
 1962: Survey by U.S.F.S. - Found a 4" square Cedar stake, replaced with 6" Concrete Monument
 1979: Survey by David B. Guthrie - Found U.S.F.S. Monument
 1986: Survey by D.R. MacNeill and Associates - Found Monument

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1994: Found 6" Round Concrete Monument with a 3" Brass Cap stamped to identify the corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1994: 6" Round Concrete U.S.F.S. Monument with a 3" Brass Cap stamped to identify the corner.
 Referenced -
 S78°W - 4" Tamarack - 5.50 feet
 S40°E - 6" Tamarack - 9.38 feet
 N84°E - 3" Cedar - 12.65 feet
 N53°E - 3" Cedar - 9.00 feet
 East - 2" Iron Pipe - 9.70 feet



Signed by D.B. Guthrie Date Nov. 5, 1994

Surveyor's Michigan License No. 22435