

# SURVEY & REMONUMENTATION

APR 25 1995  
1994 Alcona County Remonumentation Corner

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation  
Liber 1 Page 72  
RECORDED

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>7E</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

DEC 9 10 33 AM '84

*David A. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

*E.T.L.*  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

David B. Guthrie in a field survey on June 13, 1984, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1846: G.L.O. Survey by J.W. Mullett - Set Post and Referenced Beech 12 - S76E - 30 / Hem 18 - N82W - 28
  - 1917: Survey by Edw. Chapelle - Set Post and Referenced
  - 1986: Survey by D.R. MacNeill and Assoc.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1994: Found nail 1.5 feet west of the center of Sanborn Road

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1994: Replaced with 5/8" Iron Rod with a 3" Brass Cap stamped to identify the corner placed in a Monument Box.  
Referenced -  
N16°E - Utility Pole - 215.97 feet  
S03°E - Utility Pole - 386.77 feet  
S21°E - Utility Pole - 95.72 feet  
S18°E - 3" Cherry - 104.25 feet



Signed by *David A. Guthrie* Date *Dec 8, 1984*  
Surveyor's Michigan License No. 22435