

**SURVEY & REMONUMENTATION**

APR 24 1995

**COMMISSION**

1994 Alcona County Remonumentation Corner

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber Y Page 85  
**RECORDED**

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>26N</u> R <u>7E</u>	<u>H-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 ALCONA COUNTY  
 Date 12/16/94  
 County Rep E.J.L.

DEC 19 12 16 PM '94

*David B. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN  
*E.J.L.*

Register of Deeds Stamp & File Number

David B. Guthrie in a field survey on June 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

1846: G.L.O. Survey by J.W. Mullett - Set Post and Referenced Hem 6 - S6W - 20 / Hem 12 - N39E - 26

1910: Survey by W.S. Freer - Pine stake and iron bolt

1979: Survey by David B. Guthrie - Set 1/2" Iron Rod at the intersection of the center of the East West road and fencelines North and South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994: Found 1/2" Iron Rod at the intersection of the center of the East West road and fencelines North and South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1994: Replaced with a 5/8" Iron Rod with a 3" Aluminum Cap stamped to identify the Corner.  
Referenced -

- S08°W - 12" Hemlock - 35.20 Feet
- N58°W - 8" Ash - 39.10 Feet
- N45°E - 6" Aspen Stump - 30.70 Feet
- N12°E - 8" Ash - 39.85 Feet
- S45°E - 7" Ash - 42.73 Feet



Signed by *David B. Guthrie* Date Dec. 16, 1994  
Surveyor's Michigan License No. 22435