

DEC 16 1996

COMMISSION 1996 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Alcona
(County)

Located In:

Corner Code #

- | | | | | | |
|--------------------------------------|---|-----|---|----|------|
| 1. Public Land Survey | T | 26N | R | 8E | H-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Section | S | | T | R | |
| | S | | T | R | |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED

1-164
JUN 26 9 22 AM '96

County Rep. E.T.L.

Date: 6-18-96

APPROVED AND CORNER
P.A. 345 of 1990
ALCONA COUNTY

David B. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

Alcona County
Remonumentation

Number 1 Page 164

Register of Deeds Stamp & File Number

I, David B Guthrie, in a field survey on June 17, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1838 - G.L.O. Survey by Lewis Clason - Set Post and referenced Aspen 10 / N34E / 21, Aspen 06 / N39W / 12
- 1993 - Bridge Design Survey by R.S. Scott Associates - Found 1/2" Iron Rod S. / Cor. Fe. Post. / 34.43 Feet, S45°E / Mail Box / 28.08 Feet, N5°W / P. Pile / 54.85 Feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron Rod at the intersection of the center of the East West Road and a Fenceline to the South. The position of this corner is compatible with the Southeast and Southwest existing monuments at the corners of Section 34.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set a 1/2" x 18" Iron Rod with a stamped 3" Aluminum Cap 6" below the road surface. Referenced -

- N45°W - 104.44 Feet - 30"W. Pine
- S22°W - 42.41 Feet - 30" Maple
- N09°E - 54.85 Feet - Utility Pole
- S32°E - 51.22 Feet - 6" Ash
- West - 22.8 Feet - 1/2" x 18" Iron Rod with Aluminum Cap (N 1/4 corner of Sec. 3 T25N-R8E)

NOTE: Reference trees and the utility pole were marked with existing unidentified nails. Nails with tags #22435 were set adjacent to the existing nails.

Signed by David B. Guthrie

Date 06/18/96

Surveyor's Michigan License No. 24435