

SURVEY & REMONUMENTATION

DEC 16 1996

1996 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County Remonumentation
 Liber 1 Page 175
RECORDED

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>26N</u> R <u>8E</u>	I-9
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

APPROVED LAND CORNER
 P A 345 of 1990
 ALCONA COUNTY
 Date 9-20-96
 County Rep ETL
SEP 24 2 42 PM '96
David B. Guthrie
 REGISTER OF DEEDS
 ALCONA COUNTY MICHIGAN
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5		4	3		2		1			
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on July 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1843: G.L.O. Survey by Mullett and Burt - Set Post and Referenced
 Beech 14 - S23E - 42 / Beech 10 - N89W - 26
 1902: Survey by Edw. Chapelle - Set gray Boulder with crockery under it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996: Found 3/4" Iron Pipe at road intersection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.
 Referenced: S62°W - 8" Apple - 37.00 Feet
 N83°W - Fe. Cor. Post - 31.86 Feet
 S47°W - 6" Elm - 63.32 Feet
 N80°E - Utility Pole - 98.00 Feet



Signed by David B. Guthrie Date Sept. 17, 1996
 Surveyor's Michigan License No. 22435