

DEC 16 1996

1996 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 176

For corners in  
Alcona  
(County)

Located In:

Corner Code #

County Rep. E.D.L.

Date 9-20-96

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

RECORDED

SEP 24 2 42 PM '96

*David A. Guthrie*  
REGISTER OF DEEDS  
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- |                                      |                          |     |
|--------------------------------------|--------------------------|-----|
| 1. Public Land Survey                | T <u>26N</u> R <u>8E</u> | J-9 |
|                                      | T _____ R _____          |     |
|                                      | T _____ R _____          |     |
|                                      | T _____ R _____          |     |
| 2. Property Controlling in Section   | S _____ T _____ R _____  |     |
|                                      | S _____ T _____ R _____  |     |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____  |     |
|                                      | S _____ T _____ R _____  |     |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie in a field survey on July 15, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: G.L.O. Survey by Mullett and Burt - Set Post and Referenced  
W.Pine 10 N S13W - 15 / W.Birch 10 - N16W - '05

1902: Survey by Edw. Chapelle - Set gray Stone with glass crockery.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found 1/2" Iron Rod 2 Feet South of the centerline of the East West County road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.

- Referenced: N05°W - Fe. Cor. Post - 37.50 Feet
- N72°E - Fe. Post - 72.10 Feet
- S60°E - 8" Elm - 90.86 Feet
- S05°W - Fe. Cor. Post - 33.87 Feet



Signed by *David B. Guthrie*

Date Sept. 17, 1996

Surveyor's Michigan License No. 22435