

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 1 Page 177

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>26N</u> R <u>8E</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date 9-20-96
 County Alcona

RECORDED
 SEP 24 2 42 PM '96

David B. Guthrie
 REGISTER OF DEEDS
 MICHIGAN
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- 1843: G.L.O. Survey by Mullett and Burt - Set Post and Referenced Aspen 12 - ~~N~~81E - 13 / Fir 10 - S22E - 25
 - 1902: Survey by Edw. Chapelle - Set gray Boulder with glass under it.
 - 1957: Survey by Scott Eng. Co. - Found Railroad Spike, raised with T-iron.
 - 1996: Survey by Scott Eng. Co. - Found Iron 18" below the surface.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- 1996: Found 1/2" Iron Rod in Monument Box at the road intersection.

**SURVEY &
 REMONUMENTATION**
 DEC 16 1996
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1996: Placed a Brass Cap stamped to identify the corner on a 1/2" x 24" Iron Rod located in a Monument Box at the road intersection.
 Referenced: S59°W - Utility Pole - 54.54 Feet
 S36°W - 8" Ash - 95.97 Feet
 S26°E - Utility Pole - 98.50 Feet
 N76°E - 10" Aspen - 104.90 Feet



Signed by *David B. Guthrie* Date Sept. 17, 1996

Surveyor's Michigan License No. 22435