

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Remon 1 Page 24

DEC 20 1 20 PM '93

David A. Guthrie
REGISTER OF DEEDS
ALCONA COUNTY, MICHIGAN

For corners in

Alcona (County) Located In: Corner Code #
1. Public Land Survey T 26N R 8E L-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-K and rows 2-13, containing numbers 1-36.

I, David B. Guthrie a field survey on September 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set post and referenced W. Pine 28 - N66°W - 13 / W. Pine 11 - N39°E - 22
1887: Survey by A.J. Freer for the Plat of West Harrisville.
1986: Survey by D.R. MacNeill and Associates.
1993: Survey by John F. Oliver - Found 1" Iron Pipe and referenced L.C.R.C. Liber 2, Page 34.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Found 1" Iron Pipe

SURVEY & REMONUMENTATION

APR 21 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1993: Set 1/2" x 24" Iron Rod with a 3" aluminum cap stamped to identify the corner. Referenced:
N11°E - S.E. Cor. Bldg. - 44.25 Feet
N47°E - Utility Pole - 26.94 Feet
N65°W - 8" Spruce - 65.25 Feet
S10°W - 18" Box Elder - 91.00 Feet



Signed by

[Signature]

Date

12-20

Surveyor's Michigan License No. 22435