

FEB 17 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corner in COMMISSION
Alcona
(County)

Remon Liber 1 Page 50
DEC 22 1 15 PM '93

	Located In:	Corner Code #
1. Public Land Survey	T 26N R 8E	L-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

David A. Bantline
REGISTER OF DEEDS
ALCONA COUNTY MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Guthrie in a field survey on Dec. 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1843: G.L.O. Survey by Lewis Clason - Set post and referenced Cedar 22 - S64E - 13, Cedar 14 - N12W - 06

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993: Remonumentation Survey - Set corner by single proportion between the recovered Southeast and Southwest corners of Section 1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993: Set 1/2" Iron Rod with a 3" aluminum cap stamped to identify the corner. Referenced:

- S65°W - 10" Birch - 22.12 Feet
- N72°W - 8" Ash - 11.77 Feet
- N06°E - 8" Birch - 28.45 Feet
- S42°E - 8" Cedar - 19.66 Feet



Signed by *David B. Guthrie* Date 12/21/93
Surveyor's Michigan License No. 22435