

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Alcona County  
 Remonumentation  
 Liber        Page 178

For corners in  
Alcona  
 (County)

Located In:

Corner Code #

RECORDED

- |                                      |   |     |   |    |     |
|--------------------------------------|---|-----|---|----|-----|
| 1. Public Land Survey                | T | 26N | R | 8E | L-9 |
|                                      | T |     | R |    |     |
|                                      | T |     | R |    |     |
|                                      | T |     | R |    |     |
| 2. Property Controlling in Section   | S |     | T | R  |     |
|                                      | S |     | T | R  |     |
| 3. Miscellaneous Property in Section | S |     | T | R  |     |
|                                      | S |     | T | R  |     |

Date 9-26-96  
 County Alcona  
 APPROVED LAND CORNER  
 P.A. 345 of 1990  
 ALCONA COUNTY  
 REGISTER OF DEEDS STAMP & FILE NUMBER

SEP 24 2 42 PM '96

*David A. Guthrie*  
 REGISTER OF DEEDS  
 ALCONA COUNTY MICHIGAN

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, David B. Guthrie in a field survey on June 28, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1843: G.L.O. Survey by Mullett and Burt - Set Post and Referenced Cedar 10 - N11E - 12 / Cedar 6 - S42W - 10  
 1901: Survey by Edw. Chapelle - Set dark Boulder with crockery and glass under it.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1996: Found 1/2" Iron Rod at the intersection of the East West road and fencelines North and South.

**SURVEY & REMONUMENTATION**

DEC 16 1996

**COMMISSION**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1996: Set 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.  
 Referenced: N16°E - S.W. Cor. Hse. - 95.92 Feet  
 N66°E - 10" Spruce - 92.30 Feet  
 S27°E - 5" Apple - 39.92 Feet  
 S79°E - Utility Pole - 122.82 Feet



Signed by

*David B. Guthrie*

Date

Sept. 17, 1996

Surveyor's Michigan License No. 22435