

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
Remonumentation
Liber 1 Page 169

For corners in
Alcona
(County)

Located In:

Corner Code #

RECORDED

- 1. Public Land Survey T 26N - R 8E M-6
 T 26N R 9E A-6
 T R _____
 T R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

APPROVED LAND CORNER
P.A. 345 of 1990
ALCONA COUNTY
Date 9-20-96
County Rep. E.T.L.

SEP 24 2 41 PM '96

David B. Guthrie
REGISTERED SURVEYOR
MICHIGAN

Register Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced
Aspen 10 - S82W - 20 / W.Pine 9 - N51W - 33

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found Railroad Spike in a proportionate distance between the Northeast and Southeast corners of Section 13. This corner lies 7.5 feet North and 2.5 feet East of the Road intersection.

SURVEY &
REMONUMENTATION

DEC 16 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.
Referenced: N53°W - 6" Pine - 44.00 Feet
S58°W - Utility Pole - 95.70 Feet
S54°E - 6" Elm - 90.30 Feet
N73°E - Telephone cable marker - 62.30 Feet



Signed by D.B. Guthrie

Date Sept. 20, 1996

Surveyor's Michigan License No. 22435