

1996 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 1 Page 173

For corners in Alcona
 (County)

Located In:

Corner Code #

Date
 County Rep.

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY

RECORDED

SEP 24 2 42 PM '96

- | | | | | | |
|--------------------------------------|---|------------|---|-----------|---|
| 1. Public Land Survey | T | <u>26N</u> | R | <u>8E</u> | |
| | T | <u>26N</u> | R | <u>9E</u> | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | R |
| | S | | T | | R |
| 3. Miscellaneous Property in Section | S | | T | | R |
| | S | | T | | R |

M-7
 A-7

James A. Guthrie
 REGISTERED PROFESSIONAL SURVEYOR
 MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie, in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced
 W. Birch 8 - S54W - 11 / Cedar 10 - N11W - 11

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found Railroad Spike at road intersection.

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.

- Referenced: S70°W - Tele. Box - 64.25 Feet
 S48°W - Fe. Post - 51.00 Feet
 N52°E - Tele. Box - 50.35 Feet
 N32°W - Utility Pole - 122.10 Feet
 N48°W - Fe. Post - 51.90 Feet



Signed by David B. Guthrie

Date Sept. 17, 1996

Surveyor's Michigan License No. 22435