

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 1 Page 172

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>26N</u> R <u>8E</u>	<u>M-8</u>
	T <u>26N</u> R <u>9E</u>	<u>A-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED
 SEP 24 2 41 PM '96

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 REGISTER OF DEEDS
 REGISTER of Deeds Stamp & File Number

Date: 9-26-96
 County Fee: EST. L.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced
 Hem. 10 - S51W - 31 / Hem. 10 - N57W - 30

1980: Survey by D.R. MacNeill and Assoc. - Liber 178, Page 521
 References: N45°W - 48.00 Feet - 5" Locust / S80°W - 35.48 Feet - Fe. Post
 S45°E - 51.92 Feet - Fe. Post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found Railroad Spike at the intersection of the North South Road, Road East and ~~Center West~~

REMONUMENTATION

DEC 16 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.

- Referenced: S86°W - Fe. Post - 41.80 Feet
- S48°E - Fe. Cor. Post - 52.00 Feet
- S83°W - Fe. Cor. Post - 39.20 Feet
- S56°E - Conc. Marker Post - 56.17 Feet
- N64°E - Cable Marker Sign Post - 70.78 Feet



Signed by David B. Guthrie Date Sept. 17, 1996