

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Alcona County  
 Remonumentation  
 Liber 1 Page 170

For corners in  
Alcona  
 (County)

Located In:

Corner Code #

- |                                      |                          |             |
|--------------------------------------|--------------------------|-------------|
| 1. Public Land Survey                | T <u>26N</u> R <u>8E</u> | <u>M-13</u> |
|                                      | T <u>26N</u> R <u>9E</u> | <u>A-13</u> |
|                                      | T <u>25N</u> R <u>8E</u> | <u>M-1</u>  |
|                                      | T <u>25N</u> R <u>9E</u> | <u>A-1</u>  |
| 2. Property Controlling in Section   | S ___ T ___ R ___        | ___         |
| 3. Miscellaneous Property in Section | S ___ T ___ R ___        | ___         |
|                                      | S ___ T ___ R ___        | ___         |

APPROVED LAND CORNER  
 P.A. 345 of 1990  
 ALCONA COUNTY

RECORDED  
 SEP 24 2 41 PM '96

REGISTER OF DEEDS  
 MICHIGAN

Registered of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie in a field survey on July 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced  
 Beech 8 - S19W - 40 / Beech 9 - S43W - 47
- 1903: Survey by Edw. Chapelle - Beech 24 - S53W - 40
- 1994: Survey by Lewis and Lewis - Found 1/2" Iron Rod  
 Referenced: N65E - Anchor Pole - 17.39 Feet  
 N49W - Utility Pole - 52.15 Feet  
 S66E - 36" Maple - 27.52 Feet  
 S18E - 12" Basswood - 43.31 Feet

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1996: Found 1/2" Iron Rod with cap #27452 at the intersection of a North South road and fencelines East and West.

**SURVEY &  
 REMONUMENTATION**

DEC 16 1996

COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1996: Set a 1/2" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner 6" below the road surface.  
 Referenced: N65°E - Anchor Pole - 17.39 Feet  
 N49°W - Utility Pole - 52.15 Feet  
 S66°E - 36" Maple - 27.52 Feet  
 S18°E - 12" Basswood - 43.31 Feet



Signed by David B. Guthrie

Date Sept. 17, 1996

Surveyor's Michigan License No. 22435