

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 1 Page 169

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>26N</u> R <u>8E</u>	M-6
	T <u>26N</u> R <u>9E</u>	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY
 Date 9-21-96
 County Reg. E.T.L.

RECORDED

SEP 24 2 41 PM '96
David B. Guthrie
 REGISTERED PROFESSIONAL SURVEYOR

Register Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced
 Aspen 10 - S82W - 20 / W.Pine 9 - N51W - 33

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1996: Found Railroad Spike in a proportionate distance between the Northeast and Southeast corners of Section 13. This corner lies 7.5 feet North and 2.5 feet East of the Road intersection.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.
 Referenced: N53°W - 6" Pine - 44.00 Feet
 S58°W - Utility Pole - 95.70 Feet
 S54°E - 6" Elm - 90.30 Feet
 N73°E - Telephone cable marker - 62.30 Feet



Signed by D.B. Guthrie Date Sept. 20, 1996
 Surveyor's Michigan License No. 22435