

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 172

For corners in  
Alcona  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 26N R 8E  
                                  T 26N R 9E  
                                  T \_\_\_\_\_ R \_\_\_\_\_  
                                  T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section               S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous           S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Section    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

M-8  
A-8

RECORDED  
SEP 24 2 41 PM '96

APPROVED LAND CORNER  
P.A. 345 of 1990  
ALCONA COUNTY

County Reg. ESTL  
Date 9-20-96

REGISTERED PROFESSIONAL SURVEYOR  
MICHAEL J. ...

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced  
Hem. 10 - S57W - 31 / Hem. 10 - N57W - 30
- 1980: Survey by D.R. MacNeill and Assoc. - Liber 178, Page 521  
References: N45°W - 48.00 Feet - 5" Locust / S80°W - 35.48 Feet - Fe. Post  
S45°E - 51.92 Feet - Fe. Post

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1996: Found Railroad Spike at the intersection of the North South Road, Road East and fence West.

SURVEY &  
REMONUMENTATION  
  
DEC 16 1996  
  
COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1996: Set 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.  
Referenced: S86°W - Fe. Post - 41.80 Feet  
S48°E - Fe. Cor. Post - 52.00 Feet  
S83°W - Fe. Cor. Post - 39.20 Feet  
S56°E - Conc. Marker Post - 56.17 Feet  
N64°E - Cable Marker Sign Post - 70.78 Feet



Signed by David B. Guthrie Date Sept. 17, 1996

Surveyor's Michigan License No. 22435