

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Alcona  
(County)

Located In:

Corner Code #

- |                                      |   |            |   |           |             |
|--------------------------------------|---|------------|---|-----------|-------------|
| 1. Public Land Survey                | T | <u>26N</u> | R | <u>8E</u> | <u>M-10</u> |
|                                      | T | <u>26N</u> | R | <u>9E</u> | <u>A-10</u> |
|                                      | T |            | R |           |             |
|                                      | T |            | R |           |             |
| 2. Property Controlling in Section   | S |            | T | R         |             |
|                                      | S |            | T | R         |             |
| 3. Miscellaneous Property in Section | S |            | T | R         |             |
|                                      | S |            | T | R         |             |

SEP 24 2 38 PM '96

*David B. Guthrie*  
REGISTERED SURVEYOR  
ALCONA COUNTY MICHIGAN

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
9-20-96  
Registered Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

County Rep East

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Guthrie in a field survey on June 28, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced  
Hem. 7 - S52W 12 / Lynn 12 - N76W - 14
- 1901: Survey by Edw. Chapelle - Set dark gray Boulder with glass and crockery under it.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Set 1/2" Iron Rod at the intersection of the North South Road and Fenceline East and West. This location is compatible with former County Surveys and the Original Government Survey.

SURVEY &  
REMONUMENTATION

DEC 16 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Set a 1/2" x 24" Iron Rod with a Brass Cap stamped to identify the corner placed in a Monument Box.  
Referenced: N80°W - Utility Pole - 189.38 Feet  
N82°W - Telephone cable marker - 30.42 Feet  
N87°E - 6" Apple - 51.21 Feet  
S12°E - 2" Apple - 87.75 Feet



Signed by D.B. Guthrie

Date Sept. 20, 1996

Surveyor's Michigan License No. 22435