

1996 Alcona County Remonumentation Corner

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
 Remonumentation
 Liber 1 Page 170

For corners in Alcona (County) Located In: Corner Code #

1. Public Land Survey	T <u>26N</u> R <u>8E</u>	<u>M-13</u>
	T <u>26N</u> R <u>9E</u>	<u>A-13</u>
	T <u>25N</u> R <u>8E</u>	<u>M-1</u>
	T <u>25N</u> R <u>9E</u>	<u>A-1</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

APPROVED LAND CORNER
 P.A. 345 of 1990
 ALCONA COUNTY

RECORDED
 SEP 24 2 41 PM '96

REGISTER OF DEEDS
 ALCONA COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David B. Guthrie in a field survey on July 12, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by Lewis Clason - Set Post and Referenced
 Beech 8 - S19W - 40 / Beech 9 - S43W - 47
- 1903: Survey by Edw. Chapelle - Beech 24 - S53W - 40
- 1994: Survey by Lewis and Lewis - Found 1/2" Iron Rod
 Referenced: N65E - Anchor Pole - 17.39 Feet
 N49W - Utility Pole - 52.15 Feet
 S66E - 36" Maple - 27.52 Feet
 S18E - 12" Basswood - 43.31 Feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 1996: Found 1/2" Iron Rod with cap #27452 at the intersection of a North South road and fencelines East and West.

**SURVEY &
 REMONUMENTATION**

 DEC 16 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Set a 1/2" x 24" Iron Rod with an Aluminum Cap stamped to identify the corner 6" below the road surface.
 Referenced: N65°E - Anchor Pole - 17.39 Feet
 N49°W - Utility Pole - 52.15 Feet
 S66°E - 36" Maple - 27.52 Feet
 S18°E - 12" Basswood - 43.31 Feet



Signed by David B. Guthrie Date Sept. 17, 1996
 Surveyor's Michigan License No. 22435