

NOV 25 1998

1998 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in
Alcona

Located In:

Corner Code #

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 11-03-1998 At 04:37:49 pm.
LAND CORNER 9.00
OR

Alcona County
Remonumentation
Liber 1 Page 283
APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 10/24/98
County Rep [Signature]
Register of Deeds Stamp & File Number

- 1. Public Land Survey T 26NR 09E F-9
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 7-29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1843: J. MULLET - SET POST AND WITNESSED
COUNTY SURVEYOR - SET DARK BOULDER 8X10 W/CROCKERY UNDER IT
1994: NORTHEAST LAND SURVEYS (BILL WOODS, P.S. AND JOHN OLIVER, P.S.) - FOUND RAILROAD SPIKE AND RECORDED SURVEY, NO WITNESSES GIVEN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE, 2.5' WEST OF NORTH/SOUTH ROAD C/L, IN LINE WITH FENCE TO THE EAST, 4' SOUTH OF FENCE CORNER TO THE WEST

THIS CORNER POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: PLACED 3" ALCONA COUNTY CAP, STAMPED TO IDENTIFY THE CORNER, OVER 1/2" REROD IN PLACE OF RAILROAD SPIKE IN MONUMENT BOX

WITNESSES:
EAST 37.42' FENCE CORNER
S 45° W 50.46' 36" MAPLE
WEST 29.78' 24" MAPLE
N 25° W 55.52' 24" MAPLE



Signed by [Signature]
Surveyor's Michigan License No. 41922

Date November 2, 1998