

1998 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
Remonumentation
Liber 1 Page 294

For corners in

Alcona

(County)

Located In:

Corner Code #

1. Public Land Survey

T 26NR 09E

G-6

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 11-05-1998 At 04:39:24 pm.
LAND CORNER 9.00
OR

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date 10/28/98

County Rep D.R. Lewis

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 7-29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: J. MULLET - SET POST AND WITNESSED
- 1965: G.G. SLATTERY - SET 1" REBAR 1" BELOW SURFACE ON C/L OF ROADS N, S, E, W, AND MIDWAY BETWEEN SECTION CORNERS, AND WITNESSED
- 1979 AND 1980: D.R. MACNEILL, P.S. - FOUND CORNER AS RECORDED IN LIBER 180, PAGE 476, LIBER 181, PAGE 690, NO MONUMENTATION GIVEN, WITNESSED
- 1979, 1981, 1985, 1990: D.R. MACNEILL, P.S. - USED CORNER AND RECORDED VARIOUS SURVEYS, NO MONUMENTATION OR WITNESSES GIVEN
- 1997: JOHN F. OLIVER, P.S. - FOUND 3/4" BAR, NO WITNESSES GIVEN

SURVEY &
REMONUMENTATION

NOV 25 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIN, 2' EAST OF NORTH/SOUTH ROAD C/L, AND ON EAST/WEST ROAD C/L

SECTION

THIS CORNER POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: PLACED 3" ALCONA COUNTY CAP, STAMPED TO IDENTIFY THE CORNER, OVER 1/2" REROD NEXT TO 1" PIN IN MONUMENT BOX

WITNESSES:

- S 50° W 40.87' 24" MAPLE
- N 50° W 53.65' POWER POLE
- N 35° W 47.50' 24" MAPLE
- S 30° E 58.94' 24" MAPLE
- S 45° E 74.10' NW CORNER OF FOUNDATION



Signed by

Wayne T. Lewis

Date November 2, 1998

Surveyor's Michigan License No. _____

41922