

1998 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County  
Remonumentation  
Liber 1 Page 293

For corners in  
Alcona  
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>26NR 09E</u>	<u>G-7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Filed for Record in  
ALCONA COUNTY MICHIGAN  
DORIS A GAUTHIER  
On 11-05-1998 At 04:39:21 pm.  
LAND CORNER 9.00  
OR

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date: 10/28/98  
County Rep D. R. Lewis  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Wayne T. Lewis, in a field survey on 7-29, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: J. MULLET - SET POST AND WITNESSED
- 1965: G.G. SLATTERY - SET 1" REBAR, 2" BELOW SURFACE, ON C/L OF ROADS N & S AND ON FENCELINE E & W, AND WITNESSED
- 1979 AND 1981: D.R. MACNEILL, P.S. - FOUND CORNER AND RECORDED SURVEYS IN VARIOUS SURVEYS, NO MONUMENTATION OR WITNESSES GIVEN
- 1990: NORTHEAST LAND SURVEYS - FOUND 1" ROD AND RECORDED SURVEY, LIBER 266, PAGE 136, NO WITNESSES GIVEN
- 1995: DAVID B. GUTHRIE, P.S. - FOUND BOAT SPIKE AND RECORDED SURVEY, LIBER 291, PAGE 476, AND WITNESSED
- 1997: JOHN F. OLIVER, P.S. - FOUND 3/4" BAR, NO WITNESSES GIVEN

SURVEY &  
REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1" PIN ON NORTH/SOUTH ROAD C/L, AND IN LINE WITH EAST/WEST FENCE

THIS CORNER POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: PLACED 3" ALCONA COUNTY CAP, STAMPED TO IDENTIFY THE CORNER, OVER 1/2" REROD NEXT TO 1" PIN IN MONUMENT BOX

- WITNESSES:
- S 50° E 40.72' 6" ELM (TAG #22435)
  - N 50° W 43.70' FENCE POST (TAG #22435)
  - WEST 40.90' FENCE CORNER (TAG #22435)
  - S 40° W 64.65' 8" ELM (TAG #22435)



Signed by [Signature]  
Surveyor's Michigan License No. 41922

Date November 2, 1998