

1998 Alcona County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Alcona County
Remonumentation
Liber 1 Page 289

For corners in

Alcona

(County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|-------|-------------------|-------------|
| 1. Public Land Survey | | T <u>26NR 09E</u> | <u>G-11</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

Filed for Record in
ALCONA COUNTY MICHIGAN
DORIS A GAUTHIER
On 11-05-1998 At 04:38:26 pm.
LAND CORNER 9.00
OR

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date 10/24/98
County Rep DeP R. Lee
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Wayne T. Lewis, in a field survey on 7-29, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1843: J. MULLET - SET POST AND WITNESSED
- 1908: EDWARD CHAPELLE - SET LIGHT-GRAY BOULDER 12X20 W/CROCKERY UNDER IT
- 1995: D.R. MACNEILL, P.S. - FOUND PK NAIL, NO WITNESSES GIVEN

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" REROD ON NORTH/SOUTH ROAD C/L AND 6' SOUTH OF FENCE TO THE EAST

THIS CORNER POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1998: PLACED 3" ALCONA COUNTY CAP, STAMPED TO IDENTIFY THE CORNER, OVER EXISTING 1/2" REROD IN MONUMENT BOX

WITNESSES:

- S 15° E 68.32' 24" MAPLE (TAG "WITNESS POINT")
- S 45° W 98.47' POWER POLE (TAG "WITNESS POINT")
- N 60° W 65.10' POWER POLE (TAG "WITNESS POINT")
- N 85° E 35.58' FENCE CORNER



Signed by Wayne T. Lewis
Surveyor's Michigan License No. 41922

Date November 2, 1998