

**SURVEY & REMONUMENTATION**

DEC 1 6 1996

COMMISSION

1996 ALCONA COUNTY REMONUMENTATION CORNER

Alcona County Remonumentation Liber 1 Page 202

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Alcona (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>26N</u>	R	<u>9E</u>	<u>K-3</u>
	T	_____	R	_____	<u>Harrisville Twp.</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____
3. Miscellaneous Property in Section	S	_____	T	_____	_____
	S	_____	T	_____	_____

APPROVED LAND CORNER  
P A 345 of 1990  
ALCONA COUNTY  
Date \_\_\_\_\_  
County Rep \_\_\_\_\_

RECORDED  
Nov 8 8 45 AM '96  
A. Fabis  
REGISTERED  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Thomas L. Fabis, in a field survey on November 8, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1843: G.L.O. Survey by Lewis Clason - Set post & referenced: (Beech 16 - S35E - 13, Beech 14 - S22W - 30).
- 1965: State Highway Survey by G.G. Slattery - Found 3/4" Pipe (I.D.) and referenced.
- 1980: Survey (R.S. Scott W.O. 1-1267) by David Guthrie - Found 1" Pipe and referenced.
- 1986: Survey (Liber 20 Page 841) by John Oliver - Found 1" Pipe.
- 1992: MDOT Survey and L.C.R.C. (Liber 1 Page 442) by Clifford Lindgren - Found 3/4" Pipe and referenced.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- 1996: Found 3/4" Pipe 1' South of centerline of Bit. Rd. and 2 existing witnesses (N2E - 37.54' Fe. Cor. Post, S45E - 47.70' - 13" Apple) which are mentioned in the 1965, 1980 and 1992 Surveys listed above.


This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- 1996: Removed 3/4" Pipe and set a 1/2" iron rod capped with a 3" dia. brass cap, stamped to identify the corner inside a monument box.

References:

- Existing MDOT tag in 13" Apple - S45E - 47.70'
- Existing MDOT tag in Fe. Cor. Post - N2E - 37.54'
- Set tag #31591 in 4" W. Pine - S34W - 66.89'
- Set tag #31591 in 4" Twin Cherry - N20E - 45.57'
- Set tag #31591 in 7" Aspen - N65E - 64.98'



Signed by Thomas L. Fabis Date November 14, 1996

Surveyor's Michigan License No. 31591