

2

DESCRIPTIONS OF RECOVERED
POINTS.

West $\frac{1}{4}$ Corner Section 12, T26N-R9E.

Found a squared cedar stake, 24" above ground. 157' North of ck. about 35' W of ~~the~~ traveled way.

→ In line of old worm fence.

Said by Killmaster and Hastings - Adjacent land owners to be the corner.

We accept same.

New Witnesses

10" Cedar N22°W 21.5'

6" " S85°W 20.9' N. bank Creek

8" " S38°W 25.9' S. " "

NOTES FROM ^{CADE}T26N, R9E

N.W. CORNER SECTION 12

Found an iron pipe in center of E+W section line road and a $\frac{1}{4}$ of road to south, also an line of very old fence to north. Said by [] on land to SW to be the corner.

This corner is mentioned by Pettys formerly engineer for the D.M.R.R. in his testimony in the case of Agricultural Society vs. Cornell et al. Miss. State Supreme Court - Titmas as he therein describes.

Found old blaze on 12" Maple.

N55°E 43.6'

10" Maple ^{New witness} 48.1'

S-45°W-