

SURVEY &
REMONUMENTATION

DEC 18 1996

1996 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

COMMUNICATED

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

RECORDED

L1-P180
OCT 23 2 14 PM '96

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27N</u> N. S., R. <u>5E</u> E. W.	I-7
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County Remonumentation Liber Page 180

James A. Smith
REGISTERED LAND SURVEYOR
MICHIGAN

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY


Date 10-9-96
County Rep ETL

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on Sept. 27, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by T. Patterson - Set Post and referenced Hemlock 16 / S10°E / 27 / Beech 7 / N33°W / 21
 - 1927: Survey by A. Freer - Found 3 x 3 Cedar Stake (no witnesses)
 - 1952: MDOT - Placed Pavement Box with Road Construction
 - 1984: Survey by J. Oliver - Found Pav't. Box - (no witnesses)
 - 1987: Corner recorded by C. Lindgren-MDOT-Fd. Boatspike in Pav't. Box N35°W / 74.65' / Ut. Pole S38°E / 67.48' / G. Pole S70°E / 69.22' / Ch. x HDWL. N78°E / 70.86' / Ch. x HDWL.
 - 1994: Survey by F. King - Fd. Cabin Spike in Pav't. Box
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 1996: Found Pavement Box with Boat Spike with the four accessories given by C. Lindgren in 1987 above.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1996: Replaced with 1/2" Iron Rod with Brass Cap to identify the Corner. Corner is inside original Pavement Box. Referenced -
N35°W / Utility Pole / 74.70'
S70°E / Chiseled x in Headwall / 69.10'
N78°E / Chiseled x in Headwall / 70.80'
S38°E / Utility Pole / 67.40'



SIGNED BY _____ DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:
SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____