

SURVEY & REMONUMENTATION

DEC 16 1996

1996 ALCONA COUNTY REMONUMENTATION CORNER COMMISSION AND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

RECORDED

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27N</u> N. S., R. <u>5E</u> E. W.	<u>I-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County Remonumentation Lib. Page 187

Oct 23 2 15 PM '96

James A. Gauthier
REGISTRAR
MICHIGAN

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date: 10-10-96
~~REGISTER OF DEEDS STAMP AND FILING NUMBER~~

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 27 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Sur. T. Patterson-Set Post-no witnesses
- 1905: Sur. by Chappelle-Fd. Cor. (not desc.) W. Pine Stump 30/S81°E/641/4
- 1911: Sur. by Freer-Fd. 3x3 Pine Stk.-1' long-W. Pine Stump 30/S25°E/90
- 1916: Sur. by Freer-Fd. Iron Bolt-W. Pine Stump 30/S25°E/90
- 1953: MDOT constructs M-65 and places Pavement Box
- 1984: Survey by Oliver-Fd. Pavement Box (no accessories)
- 1994: Survey by F. King-Found Pipe in Pavement Box ±1' East of c/l of N-S Pav't. and ±7' South of c/l of E-W Pav't.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


1996: Found Pavement Box with 1/2" Pipe. Verified distances with MDOT Plans and F. King survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Replaced 1/2" Pipe with 1/2" Bar and Brass Cap to identify the Corner.

Referenced -

- S80°W / Chiseled X in Headwall / 56.68'
- N40°W / Util. Pole / 64.91'
- N80°E / Util. Pole / 91.40'
- S60°E / Util. Pole / 85.11'



SIGNED BY _____ DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____