

DEC 16 1996

1996 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

COMMISSION

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

RECORDED

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27N N. S., R. 5E E. W.	K-7
2. PROPERTY CONTROLLING IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County
Remonumentation
Page 1 of 1
Liberal

Oct 23 2 14 PM '96

James A. Smith
REGISTERED LAND SURVEYOR
ALCONA COUNTY

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Date: 9-20-96
County Rep. E.T.C.
REGISTER OF DEEDS, STAMP AND
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 27 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:


- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by T. Patterson-Corner given as Sugar 12 (no access.)
 - 1916: Sur. by A. Freer-finds 4x4 Cedar Sk. under Culvert (no access.)
 - 1978: Survey by N. Caldwell- fd. 1/2" Bar below pavement in line with Fence Line East, 1' West of c/l Rd. South, 4' West of c/l of Rd. North and 5' South of c/l of Rd. West.
 - 1990: Survey by L. Beauregard-fd. 1/2" Bar in line with Fence East, c/l North and South- S45°E 74.46' P.P. - East 38.62' Cor. Fence Post - S45°W 49.45' T. Pole

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 1996: Found 1/2" Bar in line with Fence Line East and centerline of Road North and South. The three accessories given by L. Beauregard above from 1990 are existing.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1996: Replaced with Pavement Box containing a 1/2" Bar and Brass Cap to identify the Corner.

Referenced -

East / Corner Fence Post / 38.45'
S45°E / Power Pole / 74.35'
S45°W / Tel. Pole / 49.40'
N30°W / 12" Ash / 89.27'



SIGNED BY _____ DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____