

DEC 1 8 1996 LAND CORNER RECORDATION CERTIFICATE

COMMISSION

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970 RECORDED

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27N N. 5E E. S., R. S., R. W.	K-8
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Alcona County
Remonumentation
Liber / Page / 8

Oct 23 2 15 PM '96

James A. Swadlow
REGISTERED
MICHIGAN

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date 10-23-96
County of Alcona
RECORDS STAMP AND
FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 27, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19__ , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey by T. Patterson - Set Post and Referenced Hemlock 4 / N20°E / 4 - Beech 5 / S16°E / 16
- 1916: Survey by A. Freer - Found Iron Bolt 10" long (no accessories)
- 1990: Survey by L. Beauregard - Found 1" Bar in c/l of Road in line with Fence to East - East 33.25' Corner Fence Post - S85°W / 33.85' / T. Pole - N75°W / 42.82' / Fence Post


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 1996: Found 1" Bar in centerline of Road with two of the accessories given by L. Beauregard above in 1990.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Replaced with Pavement Box containing a 1/2" Rod and Brass Cap to identify the Corner.
Referenced -

- S85°W / T. Pole / 33.85'
- N75°W / Fence Post / 38.60'
- N60°E / 16" Maple / 97.81'
- S20°E / 10" Elm / 78.00'



SIGNED BY [Signature] DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____