

DEC 16 1996 1996 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

COMMUNION

FILING REQUIREMENT OF ACT 74, MICH. P. 1970 RECORDED

Alcona County Remonumentation Liber Page 189

OCT 23 2 15 PM '96

Janis A. Burtch
REGISTER OF DEEDS
ALCONA COUNTY

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date 10-10-96
County Reg. E.T.L.
REGISTER OF DEEDS STAMP AND
FILING NUMBER

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>27N</u> , N. S., R. <u>5E</u> E. W.	<u>K-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 27 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1840: G.L.O. Survey by T. Patterson - Set Post and Referenced Hemlock 17 / S55°E / 08 - Cedar 14 / N48°W / 27
- 1901: Sur. by A. Freer - Fd. Cedar Stake - Cedar 14 / N48°W / 27
- 1903: Sur. E. Chapelle - Lt. Gray Boulder 12 X 14 + on top - Glass and Crockery under.
- 1916: Sur. by A. Freer - Iron Bolt given as Corner (no accessories)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 1996: Found Railroad Spike in centerline of Roads N, S, E and W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 1996: Replaced with Pavement Box containing a 1/2" Rod with Brass Cap marked to identify the Corner.

Referenced -

- N65°E / 20" Maple / 93.35'
- S75°E / 6" Apple / 127.45'
- S30°E / Ulit. Pole / 81.53'
- S55°W / 13" Elm / 176.00'



SIGNED BY _____ DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____