

DEC 16 1996

COMMISSION

1996 ALCONA COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

RECORDED

Oct 23 2 15 PM '96

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 27N, N. S., R. 5E E. W.	L-9
2. PROPERTY CONTROLLING IN SECTION	, T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S., R. E. W.	
4. LOT NO., RECORDED PLAT		
5. PRIVATE CLAIMS		

Alcona County Remonumentation Liber Page 190

Janis A. ...
REGISTERED DEEDS ORGAN

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 10-23-1996

County Rep: E, T, L.
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on Sept. 27, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 1840: G.L.O. Survey by T. Patterson - Set Post and Referenced - Beech 12 / S10°E / 25 (no other witnesses)
 - 1891: Survey by E. Chapelle - witnesses only - Maple 5 / N251/2°W / 25 Beech 14 / South / 44
 - 1903: Survey by E. Chapelle - witness only - Sugar 30 / S38°W / 89

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 1996: Found Railroad Spike in centerline of Roads N, E and W.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- 1996: Replaced with 1/2" Rod and Aluminum Cap marked to identify the Corner.
- Referenced -
- S75°E / 22" Ash / 88.54'
 - N15°W / 24" Double Maple / 63.63'
 - N50°W / 16" Maple / 53.10'
 - S65°W / 20" Oak / 151.31'



SIGNED BY [Signature] DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)