

SURVEY &
REMONUMENTATION

1996 ALCONA COUNTY REMONUMENTATION CORNER

DEC 16 1996

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970 RECORDED

COMMISSION

Alcona County
Remonumentation
Liber Page 21

Oct 23 2 16 PM '96

John A. [Signature]
REGISTERED LAND SURVEYOR

APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY

Date: 10-10-96

County Rep E.T.L.
REGISTER OF DEEDS - STAMP AND
FILING NUMBER

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 27N N. S., R. 5E E. W.	M-9
2. PROPERTY CONTROLL- ING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____	, RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

I, John F. Oliver do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on Sept. 27, 1996, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 1838: G.L.O. Survey by J. Mullett - Set Post and Referenced - Beech 7 / S55°W / 31 - Hem 12 / N48°W / 31
- 1904: Surveyor unknown - "NBT" entered in G.L.O. Notes - Hd. Maple 10 / S40°W / 23 - Hem 10 / N22°W / 19

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


1996: Found large Cedar Fence Post with USFS Tag.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1996: Placed 1/2" Rod and Aluminum Cap, marked to identify the Corner, at the South side of the Cedar Fence Post mentioned above.

Referenced -

- S75°W / 22" Red Pine / 7.91'
- N80°E / 17" double Maple / 12.80'
- N20°E / 24" Red Pine / 65.30'
- S20°E / 12" Ash / 40.40'



SIGNED BY _____ DATE 10-23-96

SURVEYOR'S MICHIGAN REGISTRATION NO. 19840

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____