

**SURVEY &
REMONUMENTATION**

MAR 04 1998

SECTION

1997 Alcona County Remonumentation Corner APPROVED LAND CORNER
P A 345 of 1990
ALCONA COUNTY
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Alcona</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>27</u> N R <u>7</u> E	<u>C-9</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Date 7/30/97
County Rep. D. B. Lee
RECORDED
Date 10-31-1997
REMON LIBER 1 PAGE 270
Time 3:30 P M
Doris A. Gauthier
Doris A. Gauthier
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel T. Kibbe, in a field survey on April 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
1838: GLO Survey by Lewis Clason - set post, referenced: Sugar 12 - S 40 W - 17 / W. Pine 26 - N 23 E - 32.
1906: County Survey by Edw. Chapelle - fd. post
1916: County Survey by Andrew J. Freer - fd. a gray boulder 6'x11'x14' "X" on top w/glass and crockery
1920: County Survey by Andrew J. Freer - fd. stone w/glass

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997: Fd. N.E.L.S. bar and cap in centerline of road on fence line East.

This corner position is compatible with county & local surveys. This corner position is accepted as a careful and faithful perpetuation of the position of the original corner.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
1997: Placed 3" Alcona County cap stamped to identify the corner over 1/2" iron rod in monument box.

- Referenced:
S35°E - 53.68' - set tag in 8" White Pine
S82°E - 36.91' - set tag in corner fence post
N37°W - 50.75' - set tag in fence post
N25°W - 80.57' - set tag in fence post
N85°W - 33.0 N.E.L.S. bar & cap

Signed by Daniel T. Kibbe
Surveyor's Michigan License No. 37278

Date October 22, 1997

